

1993

1993 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Mackinac

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 43N R 2W F-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY CLERK OF DEEDS

OCT 28 1993
AM
7 8 9 10 11 12 13 14 15 16

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column F and row 4.

I, David B. Guthrie, in a field survey on June 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: Established by William A. Burt, G.L.O. Survey
Set wood post and referenced/ 7" Tamarack - N46°E - 23 Links /
10" Tamarack - N75°W - 25 Links

1987: Survey by Richard L. Hays of Nordlund & Assoc. for U.S. Forest Service.
1989

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found 2 1/2" x 3" aluminum monument with a 3" aluminum cap stamped to identify the corner. Set in 1989 by single proportionate measurement between the Northeast and Northwest corners of Section 4. Recorded January 3, 1990 (Book D, page 38) by Richard L. Hays P.S. No. 25847.
This corner lies in the Median between the Northbound and Southbound lanes of Highway I-75.
Plat of Survey Recorded as U.S. Gov't. Plat of Survey No. 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: N73°E - 165.74 feet - Steel Post
S66°E - 156.83 feet - Steel Post
S73°W - 156.36 feet - Steel Post
N65°E - 183.46 feet - 14" Spruce
S89°E - 201.96 feet - 10" Spruce
N86°W - 193.38 feet - 15" Spruce
S71°W - 205.09 feet - 10" Spruce
East - 1.21 feet - (R=1.00') - Steel Post
The monument is a 2 1/2" x 3" aluminum mon. w/3" aluminum cap stamped to identify the corner.
(Tree references are blazed and tagged.)



Signed by [Signature] Date Sept. 27, 1993

Surveyor's Michigan License No. 22435