

1993

1993 Mackinac County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Mackinac
(County)

Located In: Corner Code ##

RECEIVED & FILED
DIANE PRA...
MACKINAC CO. MICHIGAN

001 28 1993

AM PM
718191010101010101010

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 43N R 2W G-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, David B. Guthrie, in a field survey on June 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: Established by William A. Burt, G.L.O Survey. A 10" Aspen was established as the corner and referenced: 10" Aspen - N10°W - 8 Links
- 1971: Survey by Mary C. Feindt.
- 1987: Survey by Richard L. Hays of Nordlund & Assoc. for the U.S. Forest Service.
- 1989

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993: Found 2½" x 3' aluminum monument with a 3" aluminum cap stamped to identify the corner. Set in 1989 by Richard L. Hays to replace a "T" iron previously set by Mary Feindt in 1973.
- 1989 corner by Richard L. Hays, P.S. No. 25847 recorded January 3, 1990. (Book D, page 21)

Plat of Survey Recorded as U.S. Gov't. Survey Plat of Survey No. 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: N68°W - 49.84 feet - (R=40.80') - 8" Twin Ash
- S51°W - 22.71 feet - 6" Balsam
- S70°E - 17.33 feet (R=17.27') 8" Balsam
- N52°E - 20.38 feet - (R=20.42') - 11" Balsam
- North - 2.70 feet - Steel Post

The monument is a 2½"x3' aluminum monument with a 3" aluminum cap stamped to identify the corner.

(Tree references are blazed and tagged)



Signed by David B. Guthrie Date Sept. 27, 1993

Surveyor's Michigan License No. 22435