

1993 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac (County)

Located In: Corner Code #

- 1. Public Land Survey T 43N R 2W G-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

RECEIVED & FILED
DIANE TRAP DOVICH
MACKINAC COUNTY CLERK OF DEEDS

OCT 28 1993
AM PM
71610111213141516

Register of Deeds Stamp & File Number

I, David B. Guthrie, in a field survey on June 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column G and row 3.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845: Established by J.H. Mullett, G.L.O. Survey. Set wood post and referenced: 20" Sugar Maple - N37°W - 35 Links/18" Sugar Maple - S43°W - 8 Links.
1971: Survey by Mary C. Feindt.
1972: Survey by C. Eugene Ostling.
1987: Survey by Richard L. Hays of Nordlund & Assoc. for U.S. Forest Service.
- 1989

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found 2 1/2" x 3' aluminum monument with a 3" aluminum cap stamped to identify the corner. This corner was set in 1989 by Richard L. Hays P.S. No. 25847, to replace an 8" spike which was compatible with previous references by C. Eugene Ostling (Book A, page 38- 1972) and Mary Feindt (Book A, page 73 - 1973). The Hays corner was recorded on January 3, 1989. (Book D, page 39)
Plat of Survey Recorded as U.S. Gov't. Plat of Survey No. 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: N15°W - 22.15 feet - (R=22.48') - 7" Maple
N71°E - 24.47 feet - (R=24.58') - 8" Maple
S44°E - 19.99 feet (R=19.73') - 6" Maple
S50°E - 48.35 feet - (R=48.0') - 24" Cedar
S58°W - 25.25 feet - (R=25.21') - 7" Maple
North - 5.20 feet - Steel Post

The monument is a 2 1/2" x 3' aluminum monument with a 3" aluminum cap stamped to identify the corner. (Tree references are blazed and tagged.)



Signed by [Signature] Date Sept. 27, 1993
Surveyor's Michigan License No. 22435