

**SURVEY & REMONUMENTATION**

JAN 21 1999

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
 Mackinac County Remonumentation Corner

**SECTION**

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T43N R2W T44N R2W	H-1 H-13 (Same corner Chippewa County)
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

**RECEIVED & FILED**  
 DIANE FRANKOVICH  
 MACKINAC COUNTY REGISTER OF DEEDS

DEC 30 1998  
 AM PM  
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

ACCEPTED BY THE MACKINAC COUNTY  
 SURVEY PEER GROUP AS THE  
 OFFICIAL CORNER UNDER P.A.  
 345 OF 1990 AT A MEETING  
 HELD ON 11-20-98 NEH

I, Keith R. Waters, in a field survey on October 30, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1 1/4 Corner Common to Section 3, T43N, R2W & Section 34, T44N, R2W

1840 - Original corner established by William A. Burt. Witnesses: Cedar 6, N03°W 14 links - Fir 6, N38°W 14 links.  
 1995 - LCRC, liber 9, page 245, Chippewa County corner records. Keith R. Waters, P.S. 33142, corner being reestablished as part of the Chippewa County Remonumentation Program. Reestablished corner by single proportionate measurement on the township line between recovered corners 1/2 east and 1/2 mile west. Placed a 3/4" rebar with a stamped aluminum Chippewa County Remonumentation cap at the corner position. Witnesses:  
 Nail and tag #33412 in side of 8" Black Ash, S49°W 20.06'  
 Nail and tag #33142 in side of 12" Red Maple, S75°W 48.22'  
 Nail and tag #33142 in side of 6" Black Ash, N30°E 24.55'  
 Nail and tag #33142 in side of 8" Black Ash, S08°E 36.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Mackinac County Remonumentation Program. Found the 3/4" rebar with stamped aluminum Chippewa County Remonumentation cap and all four bearing trees as called for in above mentioned Chippewa County LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 3/4" rebar with a stamped aluminum Chippewa County Remonumentation cap at the corner location.  
 Witnesses:  
 Nail and tag #33142 in side of 8" Black Ash, S49°W 20.06'  
 Nail and tag #33142 in side of 12" Red Maple, S75°W 48.22'  
 Nail and tag #33142 in side of 6" Black Ash, N30°E 24.55'  
 Nail and tag #33142 in side of 8" Black Ash, S08°E 36.52'

Note: Trees are blazed. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-23-98

Surveyor's Michigan License No. 33142



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995

T43N R2W H-1

E - 237