

**SURVEY & REMONUMENTATION**

JAN 21 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 Mackinac County Remonumentation Corner

For corners in

Mackinac

Located in:

Corner Code #

1. Public Land Survey

T 43N R 1W  
 T 43N R 2W

A-1 Same  
 M-1 Corner

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**RECEIVED & FILED**  
 DIANE FRANKOVICH  
 MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1998  
 AM \_\_\_\_\_ PM \_\_\_\_\_  
 ?|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

I, Larry R. Rogers in a field survey on December 21, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(A-1) Northwest Corner of Section 6, Township 43 North, Range 1 West.

Township corner was originally set in 1840 by W.A. Burt. In 1972 C. Eugene Ostling found and accepted a railroad spike at corner and recorded in Mackinac County Corner Records at page 39 with three power pole witnesses. In 1994 Larry R. Rogers recovered a 7/8" iron that checked well with two remaining "Ostling" power poles. Corner was recorded as part of the Chippewa County Remonumentation Program.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-1) Northwest Corner of Section 6, Township 43 North, Range 1 West.

This corner is being re-established as part of the Mackinac County Remonumentation Program. Recovered 7/8" iron on centerline of Townline Road and 2 feet West of centerline of Pea Line Road to the North. Also recovered 4 "Rogers" witnesses. Corner was replaced by a 3/4" x 24" iron with "Chippewa County Remonumentation Corner" cap in a monument box. Retied 4 existing witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-1) Northwest Corner of Section 6, Township 43 North, Range 1 West.

Corner is a 3/4" x 24" iron with "Chippewa County Remonumentation Corner" cap set in a monument box. Corner falls on centerline of Townline Road (East-West, paved) and 2 feet West of centerline of Pea Line Road (gravel) to North.

Witnesses:

Power Pole (PD3/70/72) N50°E 45.31 feet  
 Guy Pole S52°E 38.10 feet  
 Corner Fence Post S55°W 64.10 feet  
 Drill Hole in Concrete R-O-W marker N45°W 55.06 feet

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-04-98 NESH



Signed by [Signature]

Date 23 DEC 1998

Surveyor's Michigan License No. 29251

NOTE: Bearings are magnetic compass bearings not corrected for declination. Distances are to a nail in side of witness object unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975-REVISED JAN., 1983  
 REVISED OCT., 1995