

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 7 W.


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 Corner on South side of Section 34, on South boundary of Township.

CORNER MONUMENT 1/2" x 14" Iron Bar buried in E-W road

DATE MONUMENT PLACED AND WITNESSED 9-25-63

WITNESSES TO CORNER..... 10" B. Cherry (1/4 S. 34 N.B.T.) N. 17° W. 43 Lks.



CIRCLE CORNER REGISTERED

Limestone Boulder (X) N. 57° E. 74 Lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established midway between two Section Corners and in Center of old Trout Lake Road.

Corner lies 10 Links East of Plantation edge to South.

Note: 1/4 Corner for Section 3, T. 43 N., R. 7 W. lies 37 Lks. West of this corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 1/27/64
REGISTERED LAND SURVEYOR