

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 44 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 20, 21, 28, and 29

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 6/21/61

WITNESSES TO CORNER....9" B. Spruce (S 29 NBT) South 35½ Links



5" Tamarack (S 20 NBT) N 24° W 41 Links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced as set by Marcus Schaaf, Registered Land Surveyor from two Tamarack B.T.'s . Found Schaaf's post, two stump bottoms in proper position. Corner ties into old random line as noted by Schaaf.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 26, 1961  
REGISTERED LAND SURVEYOR  
Billy D. Buckler