

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner for Sections 32 and 33 on South Boundary of
Township

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 6/21/61

WITNESSES TO CORNER.... 9" Cedar (S 32 NBT) N 26° W 18½ Links



5" Cedar (S 33 NBT) N 24° E 26½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced at Cedar Post set by Marcus Schaaf, Registered Surveyor, from Original Tamarack B.T. bearing N 25° W, 18 Links. B.T. still in place, poor condition. Note: Closing corner for Sections 4 and 5, T 43 N, R 7 W lies 16 Links West.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 26, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler