

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 44 NR 7 W

Mackinac

COUNTY

DESCRIPTION OF CORNER Section Corner 8-9-16-17

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 14" H. Maple (S16 NBT) S65°E 64 Links

17" Y. Birch (S8 NB()) N18°W 36 Links

17" Y. Birch (S17 NBT) S63°W 43 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Corner by double proportionate measure from Section Corners 1 mile east, 2 miles west, 1 mile south, 2 miles north. No evidence of original Corner. Found Yl Birch marked as a witness tree bearing S61°E 1.55 chains. Blaze faces the position of Corner. Tree marked about 25 years.

SURVEYORS SEAL

SIGNED *Billy O. Buckler*
REGISTERED LAND SURVEYOR

DATE 12/28/59