

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 7 West

Mackinac COUNTY

DESCRIPTION OF CORNER Closing corner for sections 30 & 31 on west boundary of Twp.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 6-9-58

6" tamarack S 55° E 57 links. Marked "S31NET"

6" Cedar N 65° E 63 links. Marked "S30NET"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Replaced corner as set by Marcus Schaaf, Regional Surveyor. Found 2" iron pipe, found old rotten stump bottom S 50° E 30 links for tamarack bearing tree.
Note: Closing corner for sections 30 & 31, T 44 N, R 7 W, lies 18 links north of section corner 25-36, T 44 N, R 8 W. Corner lies 30 links north of swamp edge and in swamp.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler
REGISTERED LAND SURVEYOR
DATE 6-18-59