

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T44.. NR. 7.. W.

Mackinac COUNTY

DESCRIPTION OF CORNER Closing corner between Sections 4 and 5 on
North Boundary of Township.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 9" Cedar (CC NBT) S 41° W 16 Links

5" Cedar (CC NBT) S 6° E 24 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. This corner was replaced from one Tamarack B. T. bearing
S 31° W 13 Links. B. T. Plain, stump in poor condition. Found
Iron Pipe in corner, believed to be set by Marcus Sahaaf, Registered
Surveyor. Corner found by Basil McDonald, Aide, Newberry. Corner
lies N. of old Grade. Note: this corner lies 32 Links East of
Section Corner 32 and 33, T 45 N, R 7 W.

Corner was placed and witnessed January 5, 1960 with J. Halbach,
District Forester.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/23/60
REGISTERED LAND SURVEYOR
Billy D. Buckler