

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for Section 6

CORNER MONUMENT Wood Post

DATE MONUMENT PLACED AND WITNESSED 10/28/60

WITNESSES TO CORNER.....6" H. Maple (1/4s NBT) S 88° W 08 Links



5" H. Maple (1/4s NBT) N 68° E 06 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed the proportioned distance between closing corner to east and township corner to west and on line. 1/4 corner for Section 6 lies 41 links east of 1/4 for Section 31, T 45 N, R 7 W.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/23/61
REGISTERED LAND SURVEYOR
Billy D. Buckler