

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 7 W.


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner between Sections 33-34 on South Boundary of Township

CORNER MONUMENT 1/2" x 12" Iron Bar buried in South edge of old Trout Lake Road

DATE MONUMENT PLACED AND WITNESSED 9/25/63

WITNESSES TO CORNER..... 10" Red Pine (N.B.T.) S. 43° E. 107½ Lks.



CIRCLE CORNER REGISTERED

12" Jack Pine (N.B.T.) N. 11° W. 67 Lks.

Iron Fence Post S. 10° E. 50 Lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed by Single proportionate measure between Section Corners 1 mile East and 1 mile West and 50 Links North of an old Iron Fence Post.

Corner lies 10 Links East of Road Ento South.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 1/27/64
REGISTERED LAND SURVEYOR