

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MACKINAC COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. , R. <u>7</u> ^{W.} E.	<u>G-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, N. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, N. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, RLS, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7/29/76, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-13; Sec. Cor. for Secs' 33-34, only, on the South boundary of Township, set by Wm. A. Burt, D.S. , June 9, 1840.

Bearings were:

Sugar 14", N65°E, 51 Lks. and Fir 10", N60°W, 4 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-13; Corner re-established by Single Proportionate Measure, along the Township Line; using corners, 1/2 mile East and 1/2 mile West. Found no evidence of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13; Placed 1" Iron Pipe in a 3" drill hole, in Limestone Rock, to mark the corner position.

New Bearings:

12" R.Pine, S68°E, 96.7' and 6" J.Pine, S7°E, 98.1'.

NOTE:

The Closing Corner bet. Secs' 3-4, T43N R7W. is 30.4' West of this Corner.

SIGNED BY Billy D. Buckler *Billy D. Buckler* DATE 7/28/76

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

