

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>7</u> E. <u>7</u> W.	K-11
2. PROPERTY CONTROLLING IN SECTION	<u>25</u> , T. <u>44</u> N. <u>7</u> E. <u>7</u> W.	11-Sec. 25, 13-Sec. 25
3. MISCELLANEOUS PROPERTY IN SECTION	_____, T. _____ N. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-2-, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-11 Sec. Cor. 25-26-35-36, set by H. Brevoort Jr. D.S. in 1845. Bearings were: Spruce 3", S47°W, 16 lks. & Spruce 4", N49°E, 16 lks.
- 11-Sec. 25 Southwest 1/16 Corner of Section 25.
- 13-Sec. 25 Southeast 1/16 Corner of Section 25.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-11 Restored corner by D.P.M. between corners in all four directions. Corner lies in a Spruce Bog, 150' South of a small ridge.
- 11-Sec. 25 Placed corner at intersection of lines quartering the quarter section. Corner lies 112' South of R.R. Track and in open marsh.
- 13-Sec. 25 Placed corner at intersection of lines quartering the quarter section. Corner lies in opening.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminum cap at all three corners.

- K-11 New Bearings: 5" Tamarack, S79°W, 41.1' & 5" Tamarack, N35°E, 29.7'.
- 11-Sec. 25 Bearings: 6" Cedar, N35°W, 22.5' & 12" W. Pine, N52°E, 19.0'.
- 13-Sec. 25 Bearings: 5" Tamarack, S83°W, 55.5' & 8" Spruce, S32°W, 71.6'.

SIGNED BY Billy D. Buckler DATE 9-29-80

Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET

