

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>7</u> E. R. <u>7</u> W.	<u>G-8</u>
2. PROPERTY CONTROLLING IN SECTION <u>22</u>	T. <u>44</u> N. <u>7</u> E. R. <u>7</u> W.	<u>3-Sec.22</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-29, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-8 Quarter Corner bet. Sections 21-22, set by H. Brevoort Jr., D.S. in 1845. Bearings: A Tamarack 12" for Quarter Post.

3-Sec.22 North 1/16 Corner bet. Sections 21-22.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-8 Re-established 1/4 corner midway and on line bet. two re-established section corners.

3-Sec.22 Established corner midway bet. section corner to North, and 1/4 corner to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


G-8 Buried 36" T-Iron at corner. New Bearings: 8" Cedar, N30 W, 28.1' & 8" Cedar, N87°E, 44.4' & 7" Cedar, S65°E, 33.7'. Iron buried in West edge of N-S Road.

3-Sec.22 Placed 1" pipe with 4" alum. cap at cor. Bearings: 8" Cedar, S40°W, 15.4' & 7" Cedar, N35°W, 18.8' & 6" Cedar, N65°E, 36.1'. Corner lies on East side of N-S road and in line with road to East.

SIGNED BY _____ DATE 5-5-81

Billy D. Buckler
Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____