

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co

1 Corner

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>2</u> , R. <u>7</u> E. <u>W.</u>	<u>J-7</u>
2. PROPERTY CONTROLLING IN SECTION	, T. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-8, 19 81, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Corner bet. Sections 14-23, set by H. Brevoort, Jr., D.S. in 1845. Bearings were:  
 Hemlock 8", N26°E, 25 lks. and Birch 8", N43°W, 29 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Replaced corner from one Hemlock stump, no identifying marks. Position checks well with swamp edges 1½ chains West and 2½ chains East. Distance is 2641.0' to original section corner to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" alum. cap at corner. New Bearings:  
 16" W. Pine, S87°E, 74.6' and 10" Cedar, N49°E, 84.6'.

SIGNED BY

Billy D. Buckler  
 Billy D. Buckler

DATE 7-14-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

