

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

1 Corner

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. S. R. <u>7</u> E. W.	I-5
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-20, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-5 Section Corner, 10-11-14-15, set by H. Brevoort Jr., D.S. in 1845. Bearings were:
Spruce 6", $836^{\circ}E$, 38 lks. and Spruce 12", $88^{\circ}W$, 41 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-5 Found an old wood post, leaning down in the mud and some blazes on fallen trees. In determinate age. Examination notes by Geo. H. Cannon, D.S. in 1854, records: "Corner Post in small water settle," The site is a low wet bog, surrounded by low pine ridges. Examination also states: "No line or signs of line going west, at some 5 chains west of section corner a stream 15 L. C-SSW." Brevoort's notes in 1845 do not mention the stream. A stream does exist at that approx. distance. I have to believe H. Brevoort, D.S. sometimes did less than adequate work in this township and in T43N R6W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5 Placed 1" pipe with 4" alum. cap at corner. New Bearings:
 $7^{\circ}W$ Pine, $850^{\circ}W$, 13.2' and $7^{\circ}W$ Pine, $819^{\circ}E$, 21.0'

SIGNED BY _____

Billy D. Buckler
Billy D. Buckler

DATE 7-22-81

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

8887

