

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. 9 <sup>1</sup> / <sub>2</sub> R. 7 E. W.	E-12
2. PROPERTY CONTROLLING IN SECTION	32 T. 44 N. 9 <sup>1</sup> / <sub>2</sub> R. 7 E. W.	13-Sec.32
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER


I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-29, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
**E-12** 1/4 Cor. bet. Sec's. 32-33, set by H. Brevoort Jr., D.S. in 1845. Bearings were: Tam 6", S1<sup>1</sup>/<sub>2</sub>°W, 3.51 and Birch 4", N1<sup>1</sup>/<sub>2</sub>°E, 3.56 chs.  
**13-Sec.32** SE 1/16 Corner, Section 32.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
**E-12** Re-established corner midway and on line bet. two section corners.  
**13-Sec.32** Placed corner at intersection of lines quartering the SE quarter section. Also placed a 5/8" Round Iron, 138.8' West, in line with an old fence to mark a line of claimed occupation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**E-12** Placed 1" pipe with 4" alum. cap at corner. Corner lies in East end of open marsh, No witnesses available  
**13-Sec.32** Placed 3" Square Iron, 18" long in road. Bearings: 8" Scotch Pine, S62°E, 134.7' & 7" Scotch Pine, S71°W, 96.4'. Corner is 3.4' South of road centerline.

SIGNED BY Billy D. Buckler DATE 7-31-81  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_