

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>7</u> E. <u>W.</u>	H-7
2. PROPERTY CONTROLLING IN SECTION	<u>15</u> T. <u>44</u> N. <u>7</u> E. <u>W.</u>	<u>15-Sec.15</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-27, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

H-7 1/4 Cor. bet. Sec's. 15-22 set by H. Brevort Jr., D.S. in 1845. Bearings were: Birch 4, S33°E, 10 lks. and Balsam 12, N67°E, 27 lks.

15-Sec.15 West 1/16 Cor. bet. Sec's. 15-22.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-7 Placed corner midway and on line bet. Sec. Cor. 1/2 mile East and West.

15-Sec.15 Placed corner midway and on line bet. Sec. Cor. to West and 1/4 Cor. to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Placed 1" pipe with 4" alum. cap at corner. New Bearings:  
12" Spruce, S52°W, 22.1' & 12" Spruce, N40°W, 25.9' & 8" W. Birch, N50°E, 20.3'.

15-Sec.15 Placed 1" pipe 36" long, buried in East edge of N-S Road. Bearings:  
8" B. Cherry, N83°W, 48.7' & 16" W. Birch, N89°E, 71.0' & 10" H. Maple, S49°E, 54.9'

SIGNED BY \_\_\_\_\_ DATE 9-1-81

Billy D. Buckler  
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

(SEAL)