

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MACKINAC CO.

3 CORNERS

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	T. <u>44</u> N. S., R. <u>7</u> E. W.	<u>J-8, 9, 5</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 2-26, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- J-8 Center of Section 23. Not previously set.
- 9 East 1/16 Corner of Section 23. Not previously set.
- 5 North 1/16 Corner of Section 23. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-8 Corner set at intersection of east-west and north-south 1/4 lines by closed traverse.
- 9 Corner set midpoint on line between East 1/4 Corner and Center Corner of Section 23.
- 5 Corner set midpoint on line between North 1/4 Corner and Center Corner of Section 23.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument placed at all three corners.

- | | | |
|-------------------------------|---------------------------|---------------------------|
| J-8 16" R. Pine, S70°W, 30.6' | 9 12" Maple, S64°W, 11.9' | 5 6" Balsam, N87°W, 25.5' |
| 12" R. Pine, S20°E, 28.1' | 6" Maple, West, 38.7' | 6" Maple, North, 24.5' |
| 6" Maple, S68°E, 39.4' | 10" Maple, N69°W, 21.8' | 6" Balsam, N62°E, 11.5' |
| 8" Cedar, N80°E, 17.9' | 8" Maple, N12°W, 22.5' | 4" Maple, S15°W, 21.4' |

SIGNED BY Gerald L. Wiggins DATE 5-16-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET