

74

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section

S 22 T 44N R 7W 13
S 22 T 44N R 7W 12

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

12 Jul 16 1997

13 Jul 07 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(13-Sec. 22) Southeast 1/16 corner Section 22. Corner not established in the original survey. Found no subsequent record.

(12-Sec. 22) South 1/16 corner, Section 22. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 22) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The 1/16 corners to the north and east are unmonumented. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner established, I found a 1" iron pipe N12E 10.0' distant. This pipe was placed by Eino Sainio, RLS, for an approximate position. Corner placed and witnessed by T. Stark, Newberry District Office.

(12-Sec. 22) Established the corner midway and on a straight line between Center of Section 1315.97' North and Quarter corner (as monumented 7-7-97) 1315.97' South. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the monument placed, I found a "t" iron S64E 0.9' distant. This "t" iron had been placed by Eino Sainio, RLS, for an approximate corner. Monument placed and witnessed by T. Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1" pipe with 4" MDNR cap.

Blazed, scribed, and set measuring nails in the following:

8" Maple S10W 18.1' SE1/16 BT
12" Maple S86E 8.5' SE1/16 BT
10" Maple N54E 12.95' SE1/16 BT
8" Maple W24E 22.3' SE1/16 BT

Placed a 5" squared and scribed post adjacent. Bearings are magnetic.

(12) Set 1" pipe with 4" MDNR cap.

Blazed, scribed, and set measuring nails in the following:

12" M. Birch West 56.0' S1/16 BT
4" Spruce N14W 27.65' S1/16 BT
6" Aspen N59W 18.25' S1/16 BT
36" Maple W24E 53.25' S1/16 BT

Placed a 3" squared and scribed post adjacent. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

2/24/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division