

73

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S 22 T 44N R 7W 16

S 22 T 44N R 7W 4

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

4 Jul 07 1997

16 Jul 02 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 22) East 1/16 corner between Sections 22-27. Corner not established in the original survey. Found no subsequent record.

(4-Sec. 22) Northwest 1/16 corner, Sec. 22. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 22) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Quarter corner 1312.06' West and Section corner 1312.06' East. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark, Newberry District Office.

(4-Sec. 22) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. Only the 1/16 corners 1309.95' West and 1318.57' North of this position are monumented at this time. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Set 1" pipe with 4" MDNR cap.

Blazed, scribed and set measuring nails in the following:

8" N. Birch N15E 46.2' "E1/16 BT"

6" Spruce N46E 19.35' "E1/16 BT"

5" Cedar S61E 31.0' "E1/16 BT"

4" Spruce S06E 4.0' "E1/16 BT"

Placed a 4" squared and scribed post adjacent. Bearings are magnetic.

(4) Set 1" pipe with 4" MDNR cap.

Blazed, scribed, and set measuring nails in the following:

4" Cherry N59E 10.05' "NW1/16 BT"

5" Balsam S68E 8.1' "NW1/16 BT"

5" Balsam S50W 3.0' "NW1/16 BT"

5" Balsam N16W 8.05' "NW1/16 BT"

Placed a 3" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

2/24/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division