

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Hackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 44N R 7W H9

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jul 07 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(H9) Quarter corner common to Sections 22-27. Corner recorded in 1980 by Billy D. Buckler, LS as follows: Restored corner midway and on line bet. two Sec. Cors. [1979]. Buried 36" "T" iron at corner. 6" Cedar N12W 32.6', 14" Cedar S72W 53.6', centerline of road S44E 17.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H9) Original post and tamarack 8Ts not recovered. Recovered the 1979 monument, as described, at record bearing and distance from the cedar witnesses. Determined that the 1979 monument was placed erroneously and I do not accept it's location. Examination of the 1979 field notes suggests that a measurement blunder was made during the monumentation, resulting in the "T" iron being placed at the erroneous position. I established the corner midway and on a line of mean true bearing between section corners 2624.11' East and West. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986". I buried the monument beneath the gravel shoulder of Fisher Rd. The edge of the asphalt pavement is S40E (square to road) 2.5' from the monument. The centerline of the road is S40E 13.1' distant. The 1979 "T" iron was left in place as a witness to this corrected monument. Corner placed and witnessed by T.Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H9) Set 1" pipe with yellow plastic cap

33986. Blazed, scribed, and set

measuring nails in the following:

8" Cedar N02E 28.9' 1/4S NBT"

5" Maple N83W 26.6' 1/4S NBT"

10" Cedar N11W 38.0' 1/4S"

16" Cedar S77W 51.3' 1/4S"

Fd. T iron N15E 6.18'

Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2/24/98

For the Michigan Department of Natural Resources - Forest Management Division