

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 44N R 7W 68

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jul 16 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (68) Quarter corner common to Sections 21-22. Corner reestablished in 1981 by Billy D. Buckler, L.S. by proportionate measurement. Corner monument: buried T-iron at corner. Witnesses: 8" Cedar N30W 28.1', 8" Cedar N87E 44.4', 7" Cedar S65E 33.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(68) Recovered the 1981 monument, as described, in good condition, and at record bearing and distance from the Cedar NBTs NE and SE. The cedar NW has been cut. Left the monument in place and marked new accessories as described below. Corner recovered and witnessed by T. Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(68) Found T-iron, buried in W. shoulder of N-S rd. Blazed, scribed, and set measuring nails in:

10" Cedar S62E 34.2' "1/4S"

12" Cedar N89E 44.7' "1/4S"

5" Cedar S74E 30.6' "1/4S NBT"

4" W. Birch N82E 33.8' "1/4S NBT"

Placed a 3" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

2/24/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division