

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>44</u> N <u>7</u> W	<u>E7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>16</u> T <u>44</u> N <u>7</u> W	<u>10</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 30 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(E7) Corner common to Sections 16-17-20-21. 1960: Remonumented by Billy D. Buckler, RLS: "This corner was replaced at old wood post. Found one Tamarack 8.T. S51E 08 links low stump with overgrowth of scribe marks. 1" pipe with 4" brass cap. 9" White Pine S55E 11 links, 6" Tamarack S11W 24 links".
 (10-Sec. 16) South 1/16 corner between Sections 16 and 17. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E7) Recovered the 1960 monument, in good condition, at record bearing and distance from the 1960 accessories. The W.Pine is now 10" dia. The Tamarack is now 8". Overgrown blazes are plain. Left the monument in place and made new witnesses as described below.
 (10-Sec. 16) Established the corner midway and on a straight line between Quarter corner 1326.14' north and Section corner 1326.14' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E7) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in: 5" Tamarack N48W 6.95' "S17 N8T" 5" Tamarack N05W 10.8' do The 1960 wits: 10" W.Pine S53E 7.0' 8" Tamarack S12W 15.4' "S20" Bearings are magnetic. Distances are to nail with tag.	(10) Set 1" IDx36" I.pipe with 4" dia. alum. MDNR cap. Blazed, scribed, and set measuring nails in: 10" Hemlock N82W 8.55' "S1/16 8T" 6" Cedar S64W 29.1' do 8" Maple S70E 12.05' do 8" Hemlock N65E 20.45' do Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/6/02