

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Mackinac</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>7W</u>	<u>A11</u>
	T <u>44N</u> R <u>7W</u>	<u>E13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

E13 Aug 16 2005  
 A11 Jul 20 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(A11) Closing corner common to Sections 30-31 T44N-R07W. Remonumented by Billy D. Buckler RLS in 1958 at the original position as perpetuated by Marcus Schaaf, RLS. Set 1" pipe with 4" brass cap. Witnesses to corner: 6" Tamarack S55E 57 links, 6" Cedar N65E 63 links. Mr. Buckler states that the Standard corner common to Sections 25-36 T44N-R08W is 18 links south of this corner.  
 (E13) Standard Section corner common to Sections 32-33. 1961 - Remonumented by Billy D. Buckler RLS at the original position as perpetuated by Marcus Schaaf, RLS. Set 1" pipe with 4" brass cap. Witnesses to corner: 9" Cedar N26W 18.5 links, 5" Cedar N24E 26.5 links. Mr. Buckler notes that the Closing corner for Sections 4 and 5 T43N-R07W lies 16 links West of this position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A11) Recovered the 1958 monument in good condition and at record bearing and distance from the 1958 witness trees, both in good condition. Found the monumented Standard corner common to Sections 25-36 T44N-R08W 12.24' south. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. Made new marks on the 1958 Tamarack NBT.  
 (E13) Recovered the 1961 monument in good condition and at record bearing and distance from the 1961 witness trees, both in good condition. The Cedar NW has open blazes, the blazes on the Cedar NE are overgrown and new markings were made this date.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (A11) Found 1"IDx36" I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in:  
 4" Cedar N86E 13.55' mrkd "S31 NBT"  
 6" Cedar S51W 3.6' "S25 NBT"  
 10" Tamarack S56E 37.55' mrkd "S31" \*  
 7" Cedar N67E 41.8' old blazes open \*  
 Bearings are magnetic. Distances are to nail with tag. \* denotes 1958 NBT.  
 (E13) Found 1"ID I.pipe with 4" brass Mich. Dept. of Conservation cap. Set measuring nails in:  
 11" Cedar N20W 12.65' old blaze \*  
 7" Cedar N29E 17.65' mrkd "S33" \*  
 5" Cedar S29E 6.95' mrkd "S4 NBT"  
 6" Cedar S06W 15.05' do  
 Bearings are magnetic. Distances are to nail with tag. \* denotes 1961 NBT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 1/26/06