

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>7W</u>	<u>B13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>44N</u> R <u>7W</u>	<u>15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

15 Jul 21 2005
 B13 Aug 16 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B13) Quarter corner common to Section 31 T44N-R07W and Section 6 T43N-R07W. 1966 - Reestablished by F.J.Bray RLS at a position proportionate to the original record between Section corner to East and Township corner to West. Set 1" Iron pipe with 4" aluminum cap. Witnesses to corner: 7" H. Maple N66E 108.5 links, 8" (twin) H. Maple S56W 83 links, Power Pole S24E 127 links.
 (15-Sec. 31) West 1/16 corner between Section 31 T44N-R07W and Section 6 T43N-R07W. Established in 1966 by F.J.Bray RLS "on line and single proportioned distance between 1/4 corner to East and town corner to West." Set 1" iron pipe with 4" aluminum cap. Witnesses to corner: 10" H. Maple S63W 54 links, 8" H. Maple S36E 91 links. The official plat shows the 1/4 corner 20 chains east and the Township corner 19.50 chains west.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B13) Found the 1966 monument in good condition and at record bearing and distance from the 1966 witness trees. Both Maples are in good condition with overgrown blazes. The Power Pole witness checked approximately (see below for measurement). Found the monument to be 0.33' North and 0.42' West of the single proportionate position of record and accepted same as a careful and faithful reestablishment of the position of the original corner.
 (15-Sec. 31) Recovered the 1966 monument in good condition and at record bearing and distance from the H. Maple witness SE, in good condition. The H. Maple SW is now gone. Found the monument to be 0.26' North and 0.38' West of the proportionate position of record and accepted same as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B13) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 4" Cherry S89W 3.9' mrkd "1/4S NBT" 18" twin Sugar W73E 72.3' "1/4S" * 14" twin Sugar S64W 55.15' do * Power Pole S16E 84.7' Bearings are magnetic. Distances are to nail with tag.	(15) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Sugar N58E 29.8' mrkd "W1/16 BT" 8" Sugar N05E 20.05' do 8" W. Birch S43E 25.82' do 10" Sugar S31E 59.9' mrkd "W1/16" * Bearings are magnetic. Distances are to nail with tag. * denotes 1966 BT.
---	---

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1/26/06

For the Michigan Department of Natural Resources, Office of Land and Facilities