

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>7W</u>	<u>C12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>32</u> T <u>44N</u> R <u>7W</u>	<u>10</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

10 Jun 08 2005
 C12 Nov 01 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C12) Quarter corner common to Sections 31 and 32. 1845 - Established by H. Brevoort, Deputy Surveyor: North between 31&32 ...40.00 A Balsam 8 inches in diameter for quarter Section post ...80.00 Set post corner of Sections 29-30-31-32.
 (10-Sec. 32) South 1/16 corner between Sections 31 and 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C12) The original corner tree was not recovered. Reestablished the corner by single proportionate measurement to the original GLO record and on line between Section corners 2628.40' north and south.
 (10-Sec. 32) Established the corner midway and on line between Section corner 1314.20' South and Quarter corner 1314.20' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C12) Set 1"IDx36" I.pipe with 4" alum. NDNr cap. Set measuring nails in:	(10) Set 5/8"x18" rebar w/plastic cap
8" W.Birch N27E 6.93' mrkd "1/4S NBT"	"MICH DNR PS33986" flush with the surface of Hiawatha Trail. Set measuring nails and tags in:
8" W.Pine S13E 24.3' do	Power pole cut 2.5' high S22E 45.95'
5" Balsam S25W 9.82' do	12" W.Pine S32E 99.5' mrkd "S1/16 8T"
8" Spruce N65E 7.7' do	14" twin Maple N35E 168.53' do
Bearings are magnetic. Distances are to nail with tag. Sq'd an 8" Balsam, adjacent.	A 1" iron in monument box is S71E 23.85'
	The center of pavement of Hiawatha trail is South 9.2'. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1/26/06

For the Michigan Department of Natural Resources, Office of Land and Facilities