

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>7W</u>	<u>C13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>44N</u> R <u>7W</u>	<u>16</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 15 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

(C13) Corner common to Sections 31-32 T44N-R07W and Sections 5-6 T43N-R07W. 1966 - Remonumented by F.J.Bray, RLS. Certificate dated 7/18/67 states that corner was remonumented at the position of a wood post and a 1-1/4" iron pipe, found at record bearing and distance from original GLO tamarack BT. Set 1"ID iron pipe with 4" aluminum cap. New witnesses: 8" Tamarack N66E 16 links, 8" Cedar S53W 37.5 links.

(16-Sec. 31) East 1/16 corner common to Section 31 T44N-R07W and Section 6 T43N-R07W. Not established in the original survey. 1966 - Established by F.J.Bray RLS: This corner was placed midway and on line between Section corner to East and 1/4 corner to West. Set 1" Iron pipe with 4" aluminum cap. 7" Tamarack N21E 24 links, 16" W.Pine S64W 25 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C13) The monument described in the 1967 record - a 1" pipe with 4" aluminum cap - was not recovered. Found a 1-1/4" iron pipe, also noted in the 1967 record, set firm, at record bearing and distance from Mr. Bray's witnesses. The Tamarack is standing dead, the Cedar is leaning but in good condition. Accepted the 1-1/4" pipe as a careful and faithful perpetuation of the position of the original corner.

(16-Sec. 31) Recovered the 1966 monument in good condition and at record bearing and distance from the two 1966 witness trees. The W.Pine SW is 14" DBH, not 16" as described in the 1966 record. Found the monument to be 0.79' South and 1.49' West of the midway position of record and accepted same as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C13) Found a 1-1/4" iron pipe. Set measuring nails in:	(16) Found 1"ID Iron pipe with 4" alum. MDNR cap. Set measuring nails in:
5" Maple S29E 9.15' wrkd "S5 NBT"	14" W.Pine S71W 17.65' old blazes *
8" B.Spruce N09W 22.9' "S31 NBT"	7" Tamarack N27E 16.1' wrkd "E1/16"
12" Cedar N31E 35.8' "S32 NBT"	5" Tamarack S45E 16.55' "E1/16 BT"
9" Cedar S45W 24.35' wrkd "S6" *	7" Tamarack S03W 19.05' "E1/16 BT"
Bearings are magnetic. Distances are to nail with tag. * denotes 1966 NBT.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1/26/06

For the Michigan Department of Natural Resources, Office of Land and Facilities