

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>7W</u>	<u>D13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

Aug 15 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(D13) Standard Quarter corner on the south side of Section 32, T44N-R07W. 1966 - Reestablished by F.J.Bray RLS midway and on line between Section corners. No original evidence found. Set 1" Iron pipe with 4" aluminum cap. Witnesses to Corner: Power Pole No. 1361 S21W 85.5 links, 12" H.Maple N09W 31 links. Note: in his July 18, 1967 record, Mr. Bray implies that this quarter corner is common to Section 32 T44N-R07W and Section 5 T43N-R07W. According to the original GLO record, which shows that the SE corner of Section 32 and the NE corner of Section 5 are not coincident, these quarter corners are not common.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D13) Recovered the 1966 monument in good condition and at record bearing and distance from the 1966 witnesses, both in good condition. Found the monument to be 0.52' South and 1.04' West of the proportionate position of record and accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D13) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 Power pole 1361 S32W 57.1' *
 16" Sugar N03W 20.75' mrkd "1/4S" *
 7" Balsam S84W 8.05' mrkd "1/4S NBT"
 5" Balsam N65E 23.25' do
 Bearings are magnetic. Distances are to nail with tag. * denotes 1966 witness.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1/26/06

For the Michigan Department of Natural Resources, Office of Land and Facilities