

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

Mackinac Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	7-Sec.29
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	T. <u>44</u> N. _____ S., R. <u>8</u> E. _____ W. _____	9-Sec.29 6-Sec.29
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-27, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 7-Sec.29 North 1/16 Corner on East side of Section 29.
- 9-Sec.29 East 1/16 Corner of Section 29.
- 6-Sec.29 North-East 1/16 Corner of Section 29.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- 7-Sec.29 Placed corner midway between 1/4 Corner to South and Section Corner to North.
- 9-Sec.29 Placed corner midway between Center of Section and the East 1/4 Corner.
- 6-Sec.29 Placed corner at center of the NE Quarter Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 7-Sec.29 Buried 36" "T" Iron at Corner, in West side of County road. No witnesses available
- 9-Sec.29 Placed 1" pipe with 4" aluminium cap at corner.  
Bearings: 6" Spruce, N17°W, 35.0' and 8" Spruce, N79°E, 45.4'.
- 6-Sec.29 Placed 1" pipe with 4" aluminium cap at corner.  
Bearings: 12" S. Maple, N64°W, 52.0' and 6" S. Maple, N76°E, 44.1' and  
8" W. Birch, S11°E, 15.0'.

SIGNED BY \_\_\_\_\_ DATE 2-23-79

Billy D. Buckler  
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_