

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 8 W.

M a s k i n a o COUNTY

DESCRIPTION OF CORNER ~~Section corner common to Sections 20, 21, 28, 29~~

DESCRIPTION OF CORNER MONUMENT 1/2" x 36" Iron Bar buried in Center of Road

WITNESSES TO CORNER 2" W. Birch S 75° W 80 1/2 Links

10" Cedar S 59° E 80 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by proportionate measure to north and south and in center of N-S road. Placed location poster 50 links west.

Corner was placed and witnessed May 24, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 8/11/60