

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44N N.R. 8W


Mackinac COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 2-3-10-11

CORNER MONUMENT Wood post

DATE MONUMENT PLACED AND WITNESSED 10-23-70

WITNESSES TO CORNER..... 8" B. Spruce (S2 NBT) N65°E 13.5'



8" W. Spruce (S11 NBT) S66°E 5.0'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by double proportionate measure; from corner; 1 mile north; 2 miles west;  $1\frac{1}{2}$  miles east and 1 mile south. Swamp edges in all four directions check well.

Found no positive evidence of corner.

Corner lies on south edge of a wet swale.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 12-2-70