

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44N N.R. 8W


Mackinac COUNTY

DESCRIPTION OF CORNER 4 Cor. bet. Secs. 1-12

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10-22-70

WITNESSES TO CORNER..... 8" Red Pine (S NBT) S89°W 11.0'



8" Red Pine (S NBT) S36°E 15.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at old fence corner. Found fence line to west and south. Position checks with corner $\frac{1}{2}$ mile to east. Found no evidence of original corner.

Corner lies 100' east of road and in a pine plantation.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 12-2-70