

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Mackinac COUNTY
T 44N R 8W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 22-23-26-27

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 9-25-68

WITNESSES TO CORNER..... 4" W. Pine (S23 NBT) N50°E 61.6'



4" Tamarack S27 NBT) S31°W 10.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner lies in an open marsh, 60' SW of a low ridge.

This corner replaced as set by an unknown surveyor. Found an old squared post of indefinite age with a picket line to east and west. Distance north to marsh and swamp edge check as well as distance south to a small pond. Found no evidence of original spruce witnesses.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

4-4-69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing