

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Mackinac COUNTY


T 44N R 8W

DESCRIPTION OF CORNER Closing corner bet. Secs. 5-6, on north boundary of township.

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-17-68

WITNESSES TO CORNER..... 16" Y. Birch (C.C. S5 BT) S18°E 8.4'



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at an old cedar post, apparently set by unknown surveyor to mark the closing corner. Found monuments to the west for sub-division of Section 6 to line up with the location.

Note: This is a corner for Secs. 5-6 only. The standard corner for Secs. 31-32 to north is 37 lks to west of here.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler

REGISTERED LAND SURVEYOR

DATE

4-18-69

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
✓ Forestry Div., Lansing

R 4047  
Rev. 10/68