

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Mackinac COUNTY
T 44N R 8W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 27-28-33-34

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 5-8-68

WITNESSES TO CORNER..... 9" hard maple (S33 NBT) S6°W 18.8'



7" hard maple (S27 NBT) N66°E 14.6'

Squared & scribed 4" beech at Cor.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by double proportionate measure, from corners in all four directions, one mile distance.
Found no evidence of original corner or witnesses.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

3-19-69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing