

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Mackinac COUNTY  
T 44N R 8W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 5-6-7-8

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-17-68

WITNESSES TO CORNER..... 6" cedar (S5 NBT) N73°E 29.3'



7" cedar (S7 NBT) S79°W 15.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by double proportionate measure from corners in all four directions. Found no evidence of record 12" aspen for corner. Corner lies on a small island, surrounded by deep water, and covered with remains of numerous cedar stumps.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*

Billy D. Buckler

DATE

3-27-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing