

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

The Corners

FEW CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. Sec. R. <u>8</u> W.	G-3 H-3
2. PROPERTY CONTROLLING IN SECTION	T. _____ S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey of 11/21 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey of _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-3 Sec. Cor. 3-4-9-10, placed by original surveyor in 1840's. Original notes indicate this corner should fall north and west of a stream.
- H-3 1/4 Corner bet. Secs. 3-10, set during original survey of this Township.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-3 Corner re-established by proportionate measure, bet. corners; one mile East, one mile West, one mile North and two miles South. Corner placed South and East of Stream. To fit the record calls, this corner would have to be 300' North and 150' West of present position.
- H-3 Corner re-established midway and on line bet. two Sec. Corners. Corner lies in a Sag Alder marsh.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-3 Placed 1" pipe with 4" aluminium cap at both corners.
- G-3 New Bearings: 10" Cedar N32°W 45.6' and 12" Cedar S66°W 37.7'
- H-3 New Bearings: 6" B. Spruce S25°W 22.5' and 8" W. Birch N87°E 26.9'

SIGNED BY Billy D. Buckler DATE 12/15/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____