

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**  
 Mackinac Co. Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. <u>44</u> N. _____ S. _____ R. <u>8</u> E. _____ W. _____	<u>8-Sec. 27</u> <u>11-Sec. 27</u> <u>12-Sec. 27</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5-8 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 8-Sec.27 West 1/16 Corner.
- 11-Sec.27 South-West 1/16 Corner.
- 12-Sec.27 South 1/16 Corner.


**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- 8-Sec.27 1/16 Corner placed, midway bet.  $\frac{1}{4}$  Cor. to West and Center Cor. to East.
- 11-Sec.27 Corner placed, at intersection of lines, quartering the South-West Quarter Section.
- 12-Sec.27 Corner placed, midway bet.  $\frac{1}{4}$  Cor. to South and Center Cor. to North.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Placed 1" pipe at all three Corners.

- 8-Sec.27 Bearings: 8" Maple, N82°W, 23.5' and 7" Maple, N21°E, 25.6'
- 11-Sec.27 Bearings: 8" Maple, S66°W, 50.8' and 6" Maple, S14°E, 27.1'
- 12-Sec.27 Bearings: 8" Maple, S27°W, 17.1' and 7" Maple, East, 19.3'

SIGNED BY Billy D. Buckler DATE 1/30/74  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR