

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 8 West

----- Mackinac ----- COUNTY

DESCRIPTION OF CORNER section corner for sections 13 and 24 on east boundary of Twp.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 2-4-58 -----

12" white pine N 1°, W 52½ links. Marked "S13NET".

6" black spruce S 78°, W 23½ links. Marked "S24NET"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Replaced corner as set by Marcus Schaaf, Regional Surveyor. Found iron pipe, wood post in place with spruce stump bottoms, bearing S 41°, W 11 links and N 50°, W 13 links. Note: Closing corner from east lies 20 links south. Corner shown to us by J. Halbach, District Forester.

SURVEYORS SEAL

SIGNED

Billy D. Buckler

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 6-18-59