

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 8 W

M a s k i n a c COUNTY

DESCRIPTION OF CORNER ~~Section corner common to Sections 28, 29, 32, 33~~

DESCRIPTION OF CORNER MONUMENT 1/2" x 36" Iron Bar buried in center of road.

WITNESSES TO CORNER 6" Elm (twin) S 28° W 128 Links

8" B. Cherry S 76° W 59 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by proportionate measure to north and south and in center of N-S road. No evidence of original corner. Placed location poster 50 links west.

Corner was placed and witnessed May 24, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8/11/60
REGISTERED LAND SURVEYOR
Billy D. Buckler