

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

5 Corners.

Table with 3 columns: FOR CORNERS OF--, LOCATED IN--, CORNER CODE NUMBER. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-1, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-4 Center Corner, Section 12, T44N R8W.
16-Sec.12 East 1/16 Corner, on South side of Section 12.
13-Sec.12 Southeast 1/16 Corner of Section 12.
M-4 1/4 Corner on East side of Sec. 12, set by Austin Burt, D.S. in 1840. Bearings were: Hemlock 8", S13°W, 15 lks. & Hemlock 7", N21°W, 22 lks.
14-Sec.12 South 1/16 Corner, on East side of Section 12.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-4 Placed center corner at computed intersection of lines connecting opposite 1/4 corners.
16-Sec.12 Placed corner midway bet. Sec. Cor. to East and 1/4 Cor. to West.
13-Sec.12 Placed corner at intersection of lines quartering the SE Quarter Section.
M-4 Corner placed midway and on line bet. two Section Corners.
14-Sec.12 Placed corner midway bet. Sec. Cor. to South and 1/4 Cor. to North.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" alum. cap at all corners. Bearings:
L-4 12" Cedar, N25°E, 42.6' & 16" Cedar, S88°E, 57.0' & 12" R. Maple, S20°E, 22.2'
16-Sec.12 12" Cherry, S27°W, 20.1' & 8" H. Maple, S20°E, 40.9' & 10" H. Maple, East, 35.9'.
13-Sec.12 8" Cherry, N84°W, 24.1' & 8" Cherry, N4°W, 9.1' & 10" H. Maple, S27°E, 25.4'.
M-4 10" Cedar, S51°E, 34.0' & 6" Cedar, N32°W, 47.7' & 7" Spruce, S29°W, 26.5'.
14-Sec.12 5" Cedar, S79°W, 12.4' & 12" Cedar, S21°E, 32.1' & 5" Cedar, N44°E, 19.2'.

SIGNED BY Billy D. Buckler DATE 7-13-81
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



SIGNED BY Billy D. Buckler DATE 8-11-81
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY DATE
APPROVED AND SIGNED BY DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.