

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners.

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|--|--------------------|
| 1. PUBLIC LAND SURVEY | T. <u>44</u> N. <u>X</u> , R. <u>8</u> E. <u>W</u> . | <u>J-13</u> |
| 2. PROPERTY CONTROLLING IN SECTION | <u>35</u> , T. <u>44</u> N. <u>X</u> , R. <u>8</u> E. <u>W</u> . | <u>5 & 16</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION | _____, T. _____ N. _____, R. _____ E. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-3 & 11-7, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- J-13 South 1/4 corner of sec. 35. Wood Post, OITS Fir 14, N29°E, 24 lks. & Beech 5, N35°W, 32 lks.
- 5 North 1/16 corner of sec. 35. Not prev. established.
- 16 East 1/16 corner on South side of sec. 35. Original evidence destroyed by road construction - no record since the original survey.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-13 Set at position of found R.R. Spike driven in center line of blacktop road. This spike was not of record but it does fit the position shown on previous surveys by T. L. Jackson R.L.S. #293 in 1972, (Liber 1 - Pg. 159), and by Lino Sainio R.L.S. #7873 in May 1978.
- 5 Corner set M.P.O.L. bet. North 1/4 cor. and computed center of sec. 35 by closed traverse.
- 16 Set M.P.O.L. betw. the south 1/4 cor. and the S.E. sec. cor. of sec. 35. Found R.R. spike, not of record, in this position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-13 1" pipe with plastic R.L.S. cap buried in center line of road. Bearings: Power Pole, W/DNR Tag, S34°E, 88.60' & Power Pole W/DNR Tag, N63°W, 99.8' & 8" Maple, S51°W, 62.6' & 12" R. Maple, N3°W, 81.81'.
- 5 DNR Monument. Bearings: 14" H. Maple, S87°W, 52.5' & 7" Basswood, N54°W, 12.1' & 22" Maple, S72°E, 63.7' & 12" Maple, S20°E, 65.0'.
- 16 1" pipe with plastic R.L.S. cap buried in center line of road. Bearings: 8" R. Maple, S14°E, 34.0' & 16" R. Pine, S7°W, 81.3' & Power Pole W/DNR Tag, S33°W, 85.35' & Power Pole W/DNR Tag, N45°W, 65.50'.

SIGNED BY

David E. Babbitt
David E. Babbitt

DATE 11-21-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: