

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACKINAC</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 44N R 8W	H-7
	T 44N R 8W	G-7
	T 44N R 8W	I-7
2. Property Controlling in Section	S 22 T 44N R 8W	2
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on 8-5, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- H-7 1/4 Corner between 15-22. Corner placed by Billy D. Buckler, L.S. on 4-4-69. DNR Monument and 13" J. Pine, S42°E, 27.3' & 10" R. Pine, N26°E, 29.6'
 - G-7 Section Corner Common to 15-16-21-22. Corner placed by Billy D. Buckler, L.S. on 9-27-68. DNR Monument buried in road. 9" R. Pine, N45°E, 17.4' & 9" R. Pine, S30°W, 10.9' & 9" J. Pine, N19°W, 16.5'.
 - I-7 Section Corner Common to 14-15-22-23. Corner placed by Billy D. Buckler, L.S. on 9-27-68. DNR Monument. 8" R. Pine, S60°W, 18.2' & 10" R. Pine, S9°E, 26.9'.
 - 2 West 1/16 Corner between Section's 15-22. Corner placed by Billy D. Buckler, L.S. on 1-9-69. DNR Monument. 12" H. Maple, N10°E, 9.8' & 15" B. Cherry, N86°W, 23.3'.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- H-7 Pipe had been removed, found Buckler's R. Pine witness still green and J. Pine stump. Replaced monument and marked new witness trees.
 - G-7 Found Buckler's monument and witness trees, remarked top blaze on his witness trees and added another witness tree.
 - I-7 Found Buckler's corner, pipe cap was broken and both witness trees cut. Placed new monument and marked new witness trees.
 - 2 Found Buckler's 2 witness trees but monument had been removed. Replaced monument and marked two new witness trees and remarked top blaze on Buckler's witness trees.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- H-7 DNR Mon't. 12" R. Pine, N30°E, 34.8' & 4" Maple, S64°E, 13.7' & 10" Balsam, N75°W, 3.25' & 14" R. Pine, N26°E, 29.6'
 - G-7 Buried DNR Mon't. 12" R. Pine, N45°E, 17.4' & 12" R. Pine, S30°W, 10.9' & 12" J. Pine, N19°W, 16.5' & 12" J. Pine, N63°W, 43.5'.
 - I-7 DNR Mon't. 8" J. Pine, N65°E, 72.8' & 8" J. Pine, S72°W, 7.7' & 6" J. Pine, N43°W, 23.95' & 8" W. Birch, N70°W, 13.1'.
 - 2 DNR Mon't. 14" Maple, S4°E, 18.2' & 6" Maple, N43°W, 11.3' & 15" Maple, N10°E, 9.8' & 20" Cherry, N86°W, 23.3'.

Signed by Keith Sackett Date 10-10-91

Surveyor's Michigan License No. 19006