

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#89

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 44N R 8W

K11

T R

T R

T R

2. Property Controlling in Section

S 36 T 44N R 8W

3

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

K11-44365
3-44366

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jun 18 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(K11) Corner common to Sections 25-26-35-36. Corner re-monumented and recorded in 1969 by Billy D. Buckler, RLS: "This corner replaced by extending a straight line from south through the 1/4 corner and the north 1/16 corner an equal distance. Corner falls in line with old fence line to north and proper distance south of marsh. Placed 1" pipe with 4" aluminum cap. 6" Hard Maple S14W 32.4'."
(3-Sec. 36) North 1/16 corner between Sections 35-36. Corner recorded in 1969 by Billy D. Buckler, RLS: "Located this corner as set by unknown surveyor. Found iron pipe in center of M-S road and midway between fence corners. Distance south to 'quarter corner' = 1319.6'. 1 1/4" x 30" iron pipe, buried in M-S road. 12" Elm N63E 25.1', 11" J. Pine S42E 70.3'." Corner recovered in 1983 by David B. Babbitt, RLS, and used to subdivide the NE 1/4 of Section 35.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K11) Recovered Buckler's monument, as described, in good condition, and at record bearing and distance from his NBT, now 14" dia., found in good condition. Also recovered both monuments noted above, to the south. The distances south to these corners were found to be 1321.37' to the 1/16, and thence 1313.43' to the 1/4. The 1/16 corner was found 1.7' east of a straight line between the section and 1/4 corners. Despite the differences between these measurements and the previous record, I note, from the 1969 record, that the corner is in harmony with long standing occupation and with the original GLO marsh call, and also note that the monument has been long-standing and was previously used to further subdivide Section 35. I accepted the monument as the best available evidence of the position of the original corner. Left the monument in place and marked three new bearing trees as described below.
(3-Sec. 36) Recovered the monument as described, in good condition, and at record bearing and distance from the remaining 1969 J. Pine witness. Found the distance south to the 1/4 corner to be 1313.43'. Left the monument in place and marked new bearing trees as described below. I used this corner to subdivide the NW 1/4 of Section 36 at this time.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K11) Found 1" pipe with MDNR cap. Blazed, scribed, and set measuring nails in the following new bearing trees:
6" Cherry S21E 48.95' "S36 NBT"
10" Cherry S88E 72.75' "S36 NBT"
10" Red Pine N68E 23.1' "S25 NBT"
A round cedar post stands adjacent to the monument. Bearings are magnetic.

(3) found 1 1/4" iron pipe Blazed, scribed, and set measuring nails in the following:
14" J. Pine S42E 70.6' (1969 wit.)
5" J. Pine S81E 61.15' "N1/16 BT"
6" J. Pine S54E 72.9' "N1/16 BT"
10" J. Pine S26E 53.45' "N1/16 BT"
Post with location tag East 15'... Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12-10-96

For the Michigan Department of Natural Resources - Forest Management Division