

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#88

For corners in
Mackinac

(County)

Located In:

Corner Code #

11-44367

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S 36	T 44NR 8W	11
	S 6	T 44NR 8W	12
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jun 26 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(11-Sec. 36) Southwest 1/16 corner, Sec. 36. Corner not established in the original survey. Found no subsequent record.
(12-Sec. 36) South 1/16 corner, Section 36. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 36) Found no monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The controlling 1/16 corners West and South of here were not monumented. For the purposes of establishing this corner, their positions were determined by computation, being midway and on a straight line between adjacent section or 1/4 corners, as appropriate. At the position for the corner, I placed a 1" x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Distances north and east to monumented 1/16 corners were found to be 1328.34' and 1329.35', respectively.
(12-Sec. 36) Found no monumentation at the corner position. Established the corner midway and on a straight line between Center of Section 1323.12' north (recorded in 1991 by T.L. Fabis) and 1/4 corner 1323.12' south (recorded in 1991 by T.L. Fabis). At the position for the corner I buried a 1" x 36" iron pipe capped with a yellow plastic cap stamped MICH DNR LS 33986. The monument falls 4' west of the centerline of a N-S trail.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 5" Beech S87W 43.2' "SW1/16 BT" 5" Beech N87W 34.1' "SW1/16 BT" 4" Maple S86E 31.0' "SW1/16 BT" 3" Maple S54E 67.65' "SW1/16 BT" Centerline railroad North approx. 69'. Placed a 5" squared and scribed post adjacent to the monument. Bearings are magnetic.	(12) Buried a 1" pipe with plastic cap. Blazed, scribed, and set measuring nails in the following: 30" Maple S55W 63.15' "S1/16 BT" 24" Maple S41W 81.4' "S1/16 BT" Other accessories: Power Pole "E6" N26E 69.0' Fd. 5/8" iron S26W 5.15' Bearings are magnetic. Centerline of railroad approx 132.5' North.
---	---



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/10/96

For the Michigan Department of Natural Resources - Forest Management Division