

#  
87

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mackinac

Located in:

Corner Code #

(County)

1. Public Land Survey

T	R	_____
T	R	_____
T	R	_____
T	R	_____

2. Property Controlling  
in Section

S 36	T 44N	R 8W	8
S 36	T 44N	R 8W	4

3. Miscellaneous  
Property in Sec.

S	T	R	_____
S	T	R	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

4 Nov 13 1996  
8 Jun 18 1996

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 36) West 1/16 corner of Section 36. Corner not monumented in the original survey. Found no subsequent record.  
(4-Sec. 36) Northwest 1/16 corner, Section 36. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 36) Established the corner midway and on a straight line between 1/4 corner 1338.64' west (recorded in 1980 by Billy D. Buckler, and 1991 by T.L. Fabis) and Center of Section 1338.65' east (recorded by T.L. Fabis in 1991). At the position for the corner, I placed a 1" dia. x 36" iron pipe capped with a yellow plastic cap stamped MICH DNR LS 33986. The corner falls in an E-W trail.  
(4-Sec. 36) Found no monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The controlling 1/16 corners North and East of here were not monumented. For the purpose of establishing this corner, their positions were established by computation, being midway and on a straight line between Section and 1/4 corners. At the position for the corner, I placed a 1" dia. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Buried a 1" pipe with 4" MDNR cap.	(4) Set a 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails in the following bearing trees:	Blazed, scribed, and set measuring nails in the following:
5" J. Pine N58W 97.1' "N1/16 BT"	6" J. Pine N86W 11.6' "NW1/16 BT"
16" Maple N75W 75.15' "N1/16 BT"	8" J. Pine S25E 13.65' "NW1/16 BT"
4" J. Pine S60W 49.75' "N1/16 BT"	6" J. Pine S80E 21.65' "NW1/16 BT"
8" J. Pine S09E 59.25' "N1/16 BT"	12" J. Pine N42E 20.7' "NW1/16 BT"
Placed a post with a location tag North, 15'. Bearings are magnetic.	Found a "T-iron" N28E 5.43' . Placed a scribed and squared post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12-10-96

For the Michigan Department of Natural Resources - Forest Management Division