

#86

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 8W L5  
T R  
T R  
T R

2. Property Controlling  
in Section

S 13 T 44N R 8W 1

3. Miscellaneous  
Property in Sec.

S T R  
S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Jun 18 1996

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(L5) Quarter corner common to Sections 12-13. Corner restored in 1970 by Billy D. Buckler, RLS: "This corner replaced between two fence corners and in center of a fenced road, running north and south. Found no evidence of original corner, but did find an original corner 1/2 mile west to fit well. Corner monument 1" pipe with 4" aluminum cap. Witnesses to corner: 12" Hard Maple N33E 85.6', 9" Hard Maple N10W 114.0".

(1-Sec. 13) West 1/16 corner between Section 12-13. Corner not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L5) Recovered Buckler's monument as described, in good condition, approx. 4" below ground surface, and at record bearing and distance from his NBTs, both found in good condition. The above mentioned road is becoming indistinct in areas, and is no longer fenced. The fence corners noted are nearly gone. Left the corner in place, put measuring nails in the 1970 NBTs, and made two new accessories as described below.

(1-Sec. 13) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between monumented Section corner 1306.42' West and monumented Quarter corner 1306.42' East. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet appropriately stamped. Corner placed by T. Stark and O. Laapela, Newberry.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L5) Found 1" pipe with MDNR cap.

Placed measuring nails in the 1970

witnesses:

18" H. Maple N35E 85.85'

14" H. Maple N06W 114.15'

Blazed and scribed:

8" Spruce N50W 39.65' 1/4S NBT

White painted steel sign post (4090 Hunt

Club) N55E 1.15'. Bearings are

magnetic.

(1) Set 1" pipe with MDNR cap.

Blazed, scribed, and set measuring nails

in the following bearing trees:

12" Maple S10W 14.6' 1/16 BT

12" Maple N57E 14.0' 1/16 BT

12" Maple N12W 2.25' 1/16 BT

6" Beach S56W 17.5' 1/16 BT

Placed a squared and scribed cedar post

adjacent. Placed a location poster 100'

north at southside of road. Bearings

are magnetic.



Signed by Stephan J. Szyszkoski

Date 10-1-96

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division